

SCANNED
S S ENGINEERING CONSULTANTS
C-2 K [illegible] Avenue, Garia,
Kolkata—700084
Date.....
2 0 0 0 0 0 0 0



DETAIL OF POS 5
SC:- 1:5



SEC A-A
SC 1:2



SEC - B-B
SC 1:2

TECH REQUIREMENT

1. ALL WELDING TO BE DONE AS PER THE PROVISIONS OF IS:9595-1980
2. UNMENTIONED WELD SIZE TO BE TAKEN AS 10 MM
3. WELD DEPOSIT FOR HARD FACING OF THE BLADE SURFACE SHOULD BE 5 MM THK. TO 650 BHN HARDNESS — ON WORKING FACE (DIRECTION OF MATERIAL SHIFT IS SHOWN)
4. NON CO-AXIALITY OF AXES OF Ø80H; Ø120H11 & Ø140 M.R.T. SHOULD BE WITHIN THE CENTRAL AXIS SHOULD NOT EXCEED 0.1 MM.
5. NON PERPENDICULARITY OF SURFACES P&Q W.R.T. THE CENTRAL AXIS SHOULD NOT EXCEED 0.05 MM.
6. OVALITY & TAPER OF Ø80H, Ø120H11 & Ø140 SHOULD BE WITHIN HALF OF THEIR RESPECTIVE DIAMETRAL TOLERANCES.
7. TWO HALVES OF THE BLADE TO BE JOINED BY WELDING AFTER MATCHING THE EDGES SUITABLY.

AGREED TO
Sd. DT: 23.9.85
K.S. SURANA MGR. (T.R.P.)
G.R. SINGH
SUPDT (TRP & TBS)

NOTES

1. DIMENSIONS HAVE BEEN PROVIDED BY THE CONCERNED SHOP
2. MATERIAL HAS BEEN GIVEN AS PER THE AGREEMENT WITH THE INDENTOR.

		WELD METAL	2%	—	21.0	M.S	—
—	5	FLANGE Ø560/Ø190	1	27.3	27.3		Fe 410 WC IS:2062-92
085.001 00.226 A	4	SPINDLE	1	86.0	86.0		35C8 IS:2004-91
085.001 00.225	3	BLADE	10	37.10	371.0		Fe 410 WC IS:2062-92
085.001 00.224	2	PIPE Ø220x25 ASTM A519-92	1	587	587		Fe 410 WC IS:2062-92
085.001 00.223	1	SPINDLE	1	72.6	72.6		35C8 IS:2004-91
DRG. NO.	POS NO.	DESCRIPTION	QTY	UNIT WT. IN KG	TOTAL WT. IN KG	MATERIAL	REMARKS

—	SLAG CONVEYOR		1165	ASSLY	—	1:5	085.001 00.222 A
POS NO.	DESCRIPTION	QTY	UNIT WT. KG	MATERIAL	G.A. DRG. NO.	SC.	DRG. NO.

	BOKARO STEEL PLANT
SHOP	TPP & TBS
UNIT	SLAG CONVEYOR Ø560 (DPR NO. 085/001)
DESCRIPTION OF DRAWING	ASSLY. DRG. OF SLAG CONVEYOR
REVISIONS	DRAWN R.C. NAYAK — IAI — NOV 84
(1) AS PER [illegible]	CHECKED RAKESH — JOB NO 5359
	SUBMITTED B. RAM — 085.001.00
	RECOMND K.N. JHA — 322 A
	APPROVED H.R. CHAD.